



City of Prineville

387 NE THIRD STREET ♦ PRINEVILLE, OREGON 97754

DEPARTMENT OF PUBLIC WORKS ENGINEERING DEPARTMENT

Phone: (541)447-2357 FAX: (541) 447-5628

EMAIL: eklann@cityofprineville.com Website: www.cityofprineville.com

2010 2nd St Water Main Replacement Project and Street Reconstruct Project

The City of Prineville Public Works Department is planning a series of water main replacement projects. These projects will consist of the replacement of approximately 3,000 lineal feet of water main in the following streets...

<u>Street</u>	<u>Approximate Length</u>
• NW 2 nd St from the 2 nd St Egress Project to NW Deer St	2,400 lineal feet
• NW Harwood St from NW 3 rd St to NW 2 nd St	280 lineal feet
• NW Meadow Lakes Dr from NW 2 nd St south	320 lineal feet

Approximately forty-eight (48) water services will be replaced and five (5) new fire hydrants will be installed.

The existing water main in NW Harwood St is a 4" diameter wooden stave pipe that was installed in the early 1940's. The existing water main in NW 2nd St is a 6" line consisting of various materials which were installed in the 1960's. Both of these lines are deteriorating rapidly and need to be replaced. A new distribution line will be installed in NW Meadow Lakes Dr south of NW 2nd St to interconnect two (2) existing distribution systems. These existing pipes will be replaced with new 8" C-900 PVC main line which will strengthen the water distribution system, increasing available water flows for fire protection and greatly decrease maintenance related repairs. The scheduled start date for the waterline project is April 22nd, 2010 with a completion date of no later than June 4th, 2010. Every effort will be made to keep water service interruptions to a minimum.

Once the waterline replacement project is complete, the roadway surface from the end of the 2nd St Egress project to NW Meadow Lakes Dr will be completely reconstructed. All existing asphalt, aggregate base and sidewalks will be removed and reconstructed with new sidewalks and stormwater control facilities installed. The portion of NW 2nd St from NW Maple to NW Deer St will also be reconstructed to remove the failing aggregate base and an existing concrete bridge. This bridge is located at the site of the original bridge crossing over the Crooked River. The Crooked River channel has since changed and the bridge was paved over, rather than removed. Once this project is complete, NW 2nd St will receive a 2" asphalt overlay from NW Meadow Lakes Dr to NW Deer St. The road reconstruction project is expected to commence in early April and be completed in August. Every effort will be made to maintain traffic flows to minimize inconveniences during this project. The City of Prineville will provide continual progress updates as this project moves forward.

Please contact Public Works Superintendent Jerry Brummer at 541-408-2467 with any questions.